



### NV HRM

The West-Call® Novus® Home Run Module (HRM) is designed to be a remote home run controller. The HR Module is responsible for the communication between the dome light network and the master stations. The Home Run Module can be modified to support Novus® Visual and stand-alone i-Dome® devices.

- ▶ Minimum Mounting Area Required
- ▶ 16 Dome Lights per NV-HRM
- ▶ Unlimited Networking Capabilities
- ▶ Solid State Circuitry
- ▶ Voltage Test Points
- ▶ LED Status Indicators
- ▶ 63 Devices per i-Dome<sup>®</sup>/Novus<sup>®</sup> Visual HR

### VERSIONS AND MODEL NUMBERS:

STATION TYPE	MODEL NO.	PART NUMBER
Home Run Module. Remote panel supports 16 Dome Lights. Includes required electronics, PS-28 and 12x12 Hoffman Box.	NV HRM	40136014
i-Dome <sup>®</sup> /Novus <sup>®</sup> Home Run Module supports up to 63 devices. Includes required electronics, PS-28 and 12x12 Hoffman Box.	i-Dome HRM	40136015

- For use with the West-Call<sup>®</sup> Novus<sup>®</sup> system

Operating Voltage	120 VAC and 28 VDC +/-10%
Power Consumption	3 watts
Weight	15 pounds
Mounting Cabinet	12"H x 12"W x 6"D
Termination	CE100F22-5 Panduit connector for field audio connection and CE156F22-3 for power connection. RJ-45 plugs for homerun data cable, CNTR-1 network connections.
Certifications	UL-1069 for US and Canada, E139082

**NOTE:** This information should not be used for final design. Consult West-Com for total system requirements. Specifications subject to change without notice.



View West-Com's complete West-Call<sup>®</sup> line of healthcare communications solutions at [www.westcall.com](http://www.westcall.com)

West-Com Nurse Call Systems, Inc.  
2200 Cordelia Road • Fairfield, CA 94534 • 800-761-1180 • [info@westcall.com](mailto:info@westcall.com)